

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
SEP 23 1965
SEP 23 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Moore Well No. 1

Location NW-NE Sec. 36 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 4000

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: 815 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 7:30AM Day 22 Month 9 Year 1965

The Above well was plugged as follows:

219'--8 5/8" Surface pipe, cement circulated with 80 Sx. on bottom and
80 Sx. thru 2" pipe from the top.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.
cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-
placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 9/23/65
INV. NO. 1847-W