

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20270-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
10-6-70

Operator's Full Name Aspen Resources, Limited,

Complete Address Box #783, Great Bend, Kansas.

Lease Name Heskett Well No. 1

Location SE-SW-NE Sec. 12 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 3880'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Aspen Drilling Company,

Address Box #783, Great Bend, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 7:30 AM Day 3 Month 10 Year 1970

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru  
DP from 1325' to 1000'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 10-6-70

INV. NO. 2634-W