

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-179-30058-00-00

DEC 28 1965  
12-28-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rock Island Oil & Refining Company, Incorporated,

Complete Address: 321 West Douglas, Wichita, Kansas.

Lease Name Davis Well No. 1

Location NE NE-NE Sec. 2 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 2900

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No.

Operation Completed: Hour 5:00PM Day 20 Month 12 Year 1965

The Above well was plugged as follows:

290' --7" OD Surface pipe, cement circulated with 175 Sx. (6 1/2" hole below).

Circulated hole with heavy mud, set plug @ 540' and displaced 15 Sx. cement

thru DP. Heavy mud to 275', set plug with 1/4 sack hulls and displaced 15

Sx. cement thru DP. Heavy mud to 40', set plug with 1/4 sack hulls and 10

Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. J. J. J.  
Well Plugging Supervisor

DATE 12/28/65

INV. NO. 2499-u