

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1969

CONSERVATION DIVISION
Wichita, Kansas

4-14-69

15-179-20194-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Halliburton Oil Producing Company,

Complete Address: 520 Cameron Building, Oklahoma City, Oklahoma.

Lease Name Cooper Well No. 1

Location NE-NE-NE Sec. 1 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 3900

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company, Incorporated,

Address: 500 Bitting Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:30PM Day 7 Month 4 Year 1969

The Above well was plugged as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru DP
from 1325' to 1000'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from 275' to
215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/14/69
INV. NO. 9600-4

Signed: M. S. Nichols
Well Plugging Supervisor