

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20271-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1970
CONSERVATION DIVISION
Wichita, Kansas

10-12-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Heskett Well No. 1

Location NW-SW-SE Sec. 1 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 3873'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:15 AM Day 10 Month 10 Year 1970

The above well was plugged as follows:

355'--8 5/8" Surface casing, cement circulated with 150 Sx. (6 1/4" Hole).
Circulation was lost in the Cedar Hills.

Pushed bridging plug to 1350', built rock and sand bridge from 1350 to 1325'. Ran
DP to 1325' and displaced 60 Sx. cement thru DP. Pulled DP to 375' and displaced 25
Sx. cement thru DP. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10-12-70

INV. NO. 2695-4