

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20295-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
CONSERVATION DIVISION
Wichita, Kansas
10-4-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,
Complete Address 617 Union Center Building, Wichita, Kansas.
Lease Name Heskett Well No. 1
Location SE-SW-SW Sec. 1 Twp. 7 Rge. (E) (W) 26
County Sheridan Total Depth 3910'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.

Operation Completed: Hour 12:30 AM Day 1 Month 10 Year 1971

The above well was plugged as follows:

267'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1125'.
Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru
DP from 1350' to 1025'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dinkel
Well Plugging Supervisor

INVOICED
DATE 10/5/71
INV. NO. 4425-4