

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 20 1969

CONSERVATION DIVISION  
Wichita, Kansas

1-20-69

15-179-20172-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Bangle Well No. 1

Location CE/2-E/2-NW-1/4 Sec. 5 Twp. 7 Rge. (E) (W) 26

County Sheridan Total Depth 4060'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 6:00PM Day 11 Month 1 Year 1969

The Above well was plugged as follows:

282'--8 5/8" Surface casing, cement circulated with 250 Sx.  
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru  
DP from 1500' to 1175'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Deibel  
Well Plugging Supervisor

INVOICED  
DATE 1/20/69  
INV. NO. 9214-u