

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 055-20,226 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 5/17/76

Well Operator: Hartman Oil Co., Inc. (Owner / Company Name) KCC License #: 30535 (Operator's)

Address: 12950 E. 13th St. N. City: Wichita

State: Ks. Zip Code: 67203-1457 Contact Phone: ( 620 ) 277 - 2511

Lease: A. Maune Well #: #10 Sec. 31 Twp. 21 S. R. 33  East  West

- C - NE - NE Spot Location / QQQQ County: FINNEY

660' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

660' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: N/A Set at: N/A Cemented with: N/A Sacks

Surface Casing Size: 8-5/8" Set at: 362' Cemented with: 300 Sacks

Production Casing Size: 5-1/2" Set at: 4824' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: St. Louis - 4731-33'

Elevation: 2898' ( G.L. /  K.B.) T.D.: 4824' PBTD: 4784' Anhydrite Depth: 2020' (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS PER KCC - set CIBP @ 4300' w/2 sks cmt - Test csg to 500#  
set 2nd CIBP @ 1200' w/ 2 sks cmt - perforate 5-1/2" csg, 2 holes @ 1150' - test for circulation - pump 200 sks 60-40 w/ 6% gel down 5-1/2"  
(circulate cement to surface) -if no circulation - pump 200 sks 60-40 w/ 6% gel down 8-5/8" x 5-1/2" annulus

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Drilled 5/17/76

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: STAN MITCHELL

Hartman Oil Co., Inc. Phone: ( 620 ) 277 - 2511

Address: 4550 W 9 MI RD - GARDEN CITY City / State: KS.

Plugging Contractor: ALLIED KCC License #: 30535 99996 (Contractor's)

Address: P O BOX 27 - OAKLEY, Ks. Phone: ( 785 ) 672 - 3452

Proposed Date and Hour of Plugging (if known?): After 2006 wheat harvest and weather permits - around 7/1/06

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/9/06 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAY 12 2006  
KCC WICHITA



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Hartman Oil Co., Inc.  
12950 E. 13th  
Wichita, KS 67230

May 15, 2006

Re: MAUNE A #10  
API 15-055-20226-00-00  
NENE 31-21S-33W, 660 FNL 660 FEL  
FINNEY COUNTY, KANSAS

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,  


David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888