

RECEIVED
JUL 01 2005
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 185-19019-0002 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: W.D. Short Oil Co., LLC KCC License #: 33608 6679 *dyg* 6/04

Address: PO Box 729 - 102 S. River Road City: Oxford

State: Kansas Zip Code: 67119 Contact Phone: (620) 455 - 3576

Lease: S. Leesburg Unit Well #: 102 Sec. 13 Twp. 25 S. R. 13 East West

SE - NE - NW Spot Location / QQQQ County: Stafford

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~990~~ 2970 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)
KCC - SKA - 7-8-05 - AS PER RBDMS.

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-22,477 Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 10 3/4" Set at: 278' Cemented with: 225 Sacks

Production Casing Size: 7" Set at: 4114' Cemented with: 475 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3072-78, BP. @ 3493'

Elevation: 1914 (G.L. / K.B.) T.D.: 4124' P.B.T.D.: 3493' Anhydrite Depth: 710-745
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Per KCC Regs.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: William D. Short, Jr (Don)

Phone: (620) 455 - 3576

Address: PO Box 729 - 102 S. River Road City / State: Oxford, Kansas 67119

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529

Address: PO Box 467 Chase, KS 67524-0467 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-30-05 Authorized Operator / Agent: *[Signature]* *[Signature]*
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

15-185-19019-00-00

GEORGE RUSSELL WELL NO. 2

RECEIVED
JUL 01
KCC WICHITA

Date Spudded: June 30, 1942
Drlg. Completed: July 31, 1942
Potential Taken: August 3, 1942

Loc: 990' S & 330' W of N/4 Corner
of Sec. 13, Twp. 25S, Rge. 13W,
Stafford County, Kansas

From	To	Formation	From	To	Formation
0	160	Sand	2990	3074	Shale & shells
160	290	Red bed & shale	3074	3144	Broken lime
290	680	Red bed	3144	3490	Lime
680	1210	Shale & shells	3490	3550	Shale & lime
1210	1320	Salt & shale	3550	3613	Shale
1320	1660	Shale & shells	3613	3644	Lime
1660	1705	Lime broken	3644	3681	K. C. Lime
1705	1842	Lime & shale	3681	3706	Lime
1842	1950	Lime	3706	3800	Lime & shale
1950	2025	Sand & lime	3800	3908	Lime
2025	2165	Lime & shale	3908	3938	Shale & lime
2165	2365	Broken lime	3938	4044	Lime & chert
2365	2465	Lime & shale	4044	4050	Lime stks. & shale
2465	2530	Shale	4050	4115	Shale & lime
2530	2825	Shale & shells	4115	4125	Lime
2825	2990	Lime broken	4125	4124'	Total depth from cement floor level.

Elevation 1914'

Run 280' of 10-3/4" OD 28# 3 ga. "Armco" spiral weld casing; set at 278'; cemented with 225 sacks of cement.

Top of Arbuckle Lime 4113'

Run 4,145'4" of 7"OD 24# 10T grade "C", 22# 8T grade "J-55", 20# 8T grade "J-55" and 20# 8T grade "H-40" seamless casing; run 7"OD 8T DP thread form "Halcolite" male and female float collar and 7"OD 8T DP thread form "Halcolite" guide shoe; set at 4114'; cemented with 225 sacks of cement.

Drilled cement plug and hole filled up 1000' with oil in 1 hour - total fillup with oil 3900' - swabbed 346 bbls. of oil in 4 hours.

8/3/42 - Established an Echometer potential of 3000 bbls. of oil, no water, indicated capacity 7312 bbls.

Total Depth 4124'

Note: All of above footages are calculated from the cement floor level.

FLD-JL 9/9/42
LPC (3) File (1)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

F. P. Dunn
Name and title of representative of company

Subscribed and sworn to before me this the 9th day of September 1942.

My Commission expires October 21, 1944

James M. King
Notary Public

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Short, W.D. and Marjorie d/b/a Short, W. D. Oil Co.
PO Box 1
Oxford, KS 67119

July 08, 2005

Re: S LEESBURG #102
API 15-185-19019-00-02
SENENW 13-25S-13W, 4290 FSL 2970 FEL
STAFFORD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor