

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc.
Address: PO Box 2528 Liberal KS 67905
Phone: (620) 629-4200 Operator License #: 5447
Type of Well: ENHR Docket #: E-12,571
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4-5-06 (Date)
by: Richard Lacy (KCC District Agent's Name)
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (If needed attach another sheet)
Morrow Depth to Top: 4934 Bottom: 4972 T.D. 5320
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API Number: 15-129-00423 10311-00-01
Lease Name: Wibarton Morrow Sand Unit
Well Number: 1801 W
Spot Location (QQQQ): - - NW - SE
1980 Feet from ☐ North / ☒ South Section Line
1980 Feet from ☒ East / ☐ West Section Line
Sec. 33 Twp. 34 S. R. 41 ☐ East ☒ West
County: Morton
Date Well Completed: 4-30-97 Spuds
Plugging Commenced: 4-5-06
Plugging Completed: 4-6-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 $\frac{5}{8}$	1501	—
				5 $\frac{1}{2}$	5118	1484

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb hulls & 25 sx cmt to plug perfs from 4934 to 4734. 5 $\frac{1}{2}$ stuck @ base of 8 $\frac{5}{8}$. Shot loose & circ. hole w/ mud & mixed 50 sx 1484 to 1334 30 sx 350 to 250, 10 sx 40 to 0 Capped 8 $\frac{5}{8}$ 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORION PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address)

SUBSCRIBED and SWORN TO before me this


9 day of May

2006

Anita Peterson
Notary Public

My Commission Expires:

Oct. 1, 2009



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 12 2006

KCC WICHITA