

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC 5/12/06 per CP-1

Lease Operator: AGV Corp.
Address: 123 N. Main Attica, Kansas 67009
Phone: (620) 254-7222 Operator License #: 5039
Type of Well: Gas oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/25/06 (Date)
by: Steve VanGieson (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 3938 Bottom: 4249 T.D. 4356
Stalnaker Depth to Top: 2983 Bottom: N/A T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-191-20173-00-00
Lease Name: Coffman
Well Number: #1
Spot Location (QQQQ): SE - NE -
1980 Feet from North / South Section Line
60500 Feet from East / West Section Line
Sec. 26 Twp. 32 S. R. 4 East West
County: Sumner
Date Well Completed: 1-22-70
Plugging Commenced: 4-28-06
Plugging Completed: 4-28-06

KCC 5-12-06 per CP-1

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0	252	8 5/8	252'	None
Production	Oil, Gas, Water	0	4054'	4 1/2	4054	2060

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perfs 3970-3978. CIBP @ 3950. Perfs 2994' Sqz w/ 100 sacks cement. Perfs @ 2984-2990. CIBP @ 2950, 2 sx cement on top w/ dump bailer.
Shot casing off @ 2060'. Spot 35 sx thru casing @ 603', Circulated thru casing to surface w/ 100 sx. Pulled casing and top off w/ 15 sx. (Total 150 sx 60/40 poz, 4% gel). Job Complete 11:30 AM on 4-28-06 by Allied Cementing, ticket # 23351

Name of Plugging Contractor: Genesis Well Service License #: 33093
Address: PO Box 464 Pratt Kansas 67124

Name of Party Responsible for Plugging Fees: Operator
State of Kansas County, Harper, ss.


Larry G Mans (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry G Mans

(Address) 123 N Main Attica Ks 67009

SUBSCRIBED and SWORN TO before me this 11 day of May, 2006

Kayon Tompkinson My Commission Expires: April 24, 2007
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 12 2006

KCC WICHITA

per