

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: AGV Corp.  
Address: 123 N. Main Attica, Kansas 67009  
Phone: (620) 254-7222 Operator License #: 5039  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4/25/06 (Date)  
by: Steve VanGieson (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Stalnaker Depth to Top: 2991 Bottom: 2995 T.D. 2995  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-191-22404-00-00  
Lease Name: Ray  
Well Number: #1  
Spot Location (QQQQ): 190°E - N/2 - SE - NE  
1600 Feet from  North /  South Section Line  
30 470 Feet from  East /  West Section Line  
Sec. 26 Twp. 32 S. R. 4  East  West  
County: Sumner  
Date Well Completed: 8-11-03  
Plugging Commenced: 4-27-06  
Plugging Completed: 4-27-06

KCC 5/15/06  
PPT.  
Figs edited

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Water	0	267	8 5/8	267	None
Production	Oil, Gas, Water	0	2991	4 1/2	2991	1634'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

OPEN HOLE COMPLETED FROM 2991 - 2995'. SET CIBP @ 2940', CAP W/ 2 SX CEMENT THRU DUMP BAILER, SHOT CASING OFF @ 1634'. SPOT 35 SX @ 603'. PULL CASING TO 324', CIRCULATED CEMENT TO SURFACE W/ 95 SX. PULLED CASING AND TOP OFF W/ 15 SX. JOB COMPLETE 11:30 AM 4-27-06 BY ALLIED CEMENTING, TICKET # 23126

Name of Plugging Contractor: Genesis Well Service License #: 33093  
Address: PO Box 464 Pratt Kansas 67124

Name of Party Responsible for Plugging Fees: Operator  
State of Kansas County, Harper, ss.

Larry G Mans (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry G Mans

(Address) 123 N Main Attica Ks 67009

SUBSCRIBED and SWORN TO before me this 11 day of May, 2006

Kayan Tompkinson My Commission Expires: April 24, 2007  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT