

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-065-23169-00-00

LEASE NAME Windholz "C" KCC

WELL NUMBER 2-19 ^{5116106A} per C-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

770 Ft. from S Section Line

1,670 Ft. from ^WE Section Line

SEC. 19 TWP. 10S RGE. 22 ~~E~~ or (W)

COUNTY Graham

Date Well Completed 5-5-06

Plugging Commenced 5-5-06

Plugging Completed 5-5-06

LEASE OPERATOR RUSSELL OIL, INC.

ADDRESS PO Box 1459, Plainfield, IL 60544

PHONE (815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-5-06 (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	218'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push plug to 1,850', pump 25 sax cement on plug thru drill pipe; push plug to 982', pump 100 sax cement on plug thru drill pipe; push plug to 208', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address BOX 709, RUSSELL, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Jack P. Beeman, Sec.-Treas. (Employee of ~~Operator~~ Contractor or (Operator), above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO BOX 709, RUSSELL, KS 67665

SUBSCRIBED AND SWORN TO before me this 10th day of MAY, 2006

Debra Phillips
Notary Public



RECEIVED

MAY 15 2006

KCC WICHITA

My Commission Expires: