

CONSERVATION DIVISION
WICHITA STATE OFF. BUILDING
130 S MARKET ROOM 2078
WICHITA KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

APR NUMBER 15-111-20295-00-00
LEASE NAME Nuessen
KCC Plot 5/18/06
Per CPA/3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER B-10
3599
3580 Ft. from S Section Line
1307
1300 Ft. from E Section Line

LEASE OPERATOR Schankie Well Service, Inc.
ADDRESS 1006 SW Blvd, Box 397 Madison, KS 66860
PHONE#(620) 437-2595 OPERATORS LICENSE NO. 6470

SEC. 31 TWP. 21 SRGE. 12 (E) or (W)
COUNTY Lyon
Date Well Completed 12-27-80
Plugging Commenced 4-10-06
Plugging Completed 4-11-06

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-10-06 (date)
by Mike Heffern, District #3 (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation Bartlesville Depth to Top 1927' Bottom 1971' T.O. 1985'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	55'	None
				4 1/2"	1984'	762'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot cement plug down 2 3/8" tubing @ 1878' w/5sx cement & 3sx gel.
Ripped pipe @ 762', Spot cement plug down 4 1/2" casing @ 725' w/17sx
cement & 2sx gel, Spot cement plug down 4 1/2" casing @ 150' w/50sx to
surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Schankie Well Service, Inc. License No. 6470

Address 1006 SW Blvd, Box 397 Madison, KS 66860

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Schankie Well Service, Inc.

STATE OF Kansas COUNTY OF Greenwood, ss.

Randall Schankie, Secretary (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.


(Signature) Randall Schankie, Sec

(Address) Box 397 Madison, KS 66860

SUBSCRIBED AND SWORN TO before me this 30th day of April, 192006

Cynthia L. Finch
Notary Public

My Commission Expires: 4-23-06

 CYNTHIA L. FINCH
NOTARY PUBLIC - STATE OF KANSAS
MY APPT. EXP

Form CP-4
Revised 05-88

RECEIVED
MAY 18 2006
KCC WICHITA

PCF

WELL LOG

Company Nuessen Oil Co.
 Farm Nuessen
 Well B - 10
 Location 940' FSL - 1300' FEL 31-21S-12E Lyon Co., KS
 Commenced 12/22/80
 Completed 12/27/80
 Casing 55' 8 5/8" cemented with 25 sacks
 1984' 1 1/2" cemented with 60 sacks
 Contractor Jackman & Jackman
 Production Testing
 Total depth 1985

Soil & Clay	0	12
Shale & Lime	42	109
	109	550
Shale	550	805
Lime	805	808
Water Sand	808	955
Lime	955	1166
Shale	1166	1199
Lime	1199	1378
Shale	1378	1425
Shale & Shells	1425	1769
Shale	1769	1927
Shaley sand & Sand	1927	1971
Shalw	1971	1985

0' is 4' above ground level.

RECEIVED
 MAY 18 2006
 KCC WICHITA