

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Shakespeare Oil Company, Inc.

Address: 202 West Main Street

Phone: (618) 548-1585 Operator License #: 7311

Type of Well: Oil D&A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 4/9/06 (Date)

by: Herb Dinas (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

N/A Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15-109-20763-00-00

Lease Name: Frey

Well Number: 2-15

Spot Location (QQQQ): E/2 - SE - NW - SE 1623 Feet from North / South Section Line

1619 Feet from East / West Section Line

Sec. 15 Twp. 13 S. R. 32 East West

County: Logan

Date Well Completed: N/A

Plugging Commenced: 4/9/06

Plugging Completed: 4/10/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Rotary mud from 4620' to 2425', 2300' to 1750', 1250' to 275', 75' to 40'.

Cement plugs from 2425' to 2300', 1750' to 1250', 275' to 75', 40' to 0', 15 sx rathole, 10 sx mousehole.

A total of 200 sx 60/40 Pozmix, 6% gel & 1/4# Floseal was placed by drillpipe and cemented by Allied Cementing Co., Inc.

RECEIVED

MAY 15 2006

KCC WICHITA

Name of Plugging Contractor: Murfin Drilling Co. Rig #14 License #: 30606

Address: 250 N. Water, Suite 300 Wichita, KS


Name of Party Responsible for Plugging Fees: Shakespeare Oil Company, Inc.

State of Illinois County, Marion, ss.

Donald R. Williams, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Donald R. Williams

(Address) 202 West Main St., Salem, IL 62881



Subscribed and SWORN TO before me this 11th day of May, 2006

Melissa A. McCormick My Commission Expires: 4-11-07 Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT