

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline
Address: 4700 Hwy. 56 P.O. Box 20010 Owensboro, Kentucky 42304-0010
Phone: (270) 852-4490 Operator License #: 33097
Type of Well: Gas Storage Observation GSI Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/19/2006 (Date)
by: Steve Korf / Taylor Herman (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
McLouth Ss. Depth to Top: 1428' Bottom: 1434' T.D. 1434'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-087-19016-00-01
Lease Name: McLouth Gas Storage
Well Number: 0-1
Spot Location (QQQQ): NW - NW - NW - SE
2334 Feet from North / South Section Line
2357 Feet from East / West Section Line
Sec. 17 Twp. 9 S. R. 20 East West
County: Jefferson
Date Well Completed: 1/1/1944
Plugging Commenced: 4/27/2006
Plugging Completed: 4/27/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
McLouth Sandstone	Gas (1428'-1434')	0	1420	7"		
		1414.5	1434	5.5"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 2 3/8 work string tubing to 1434'. Establish flow rate through tubing-spot 60 sks. OWC cement @ T.D. Pull 210' of tubing to 1222', pump OWC cement through tubing and fill 7" casing solid to surface. Pull tubing and top well off to surface with 196 sks. OWC cement. Tied to well at surface and pressured up with cement to 300#. Shut in well.

(OWC cement = Class A w/6% cal. & 2 % gel)

Name of Plugging Contractor: Consolidated Well Services License #: 31440

Address: 211 W. 14th St. Chanute, Kansas 66720

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse D. Mark Rouse (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse

(Address) P.O. Box 20010 Owensboro, Ky. 42304-0010

SUBSCRIBED and SWORN TO before me this 10th day of May, 2006

Elizabeth Morris My Commission Expires: 7-29-06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 15 2006
KCC WICHITA

PKT