

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

RECEIVED

MAY 10 2006

KCC WICHITA

Lease Operator: C & S Oil

Address: P.O. Box 41, Neosho Falls, KS 66758

Phone: (620) 365-0919 Operator License #: 30102

Type of Well: ENHR Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 04/04/2006 (Date)

by: Clayton Titel (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) squirrel Depth to Top: NA Bottom: NA T.D. 950'

API Number: 15 - 207-19719-00-00

Lease Name: Remlinger

Well Number: 12

Spot Location (QQQQ): NW - NE - SE - NW

3656 Feet from North / South Section Line

3159 Feet from East / West Section Line

Sec. 24 Twp. 23 S. R. 16 East West

County: Woodson

Date Well Completed: NA

Plugging Commenced: 04/04/2006

Plugging Completed: 04/04/2006, 12:30 PM

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Squirrel production and surface.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

1" pipe was ran into the 2" casing to 900'. Cement was pumped into the 1" pipe until cement circulated from the 2" casing at surface. The 1" pipe was removed. 1" pipe was ran into the 2" and 12" annulus to 700'. 15 sacks of cement were pumped into the 1" pipe at 700'.

The 1" pipe was pulled to 230'. Cement was pumped into the 1" pipe until cement circulated from the 2" and 12" annulus at surface. The 1" pipe was removed. Displacement was filled from surface. 144 sacks of cement were pumped into this well.


Name of Plugging Contractor: Christenson, Robert dba Hurricane Truck Services License #: 92006 30102

Address: PO Box 782228, Wichita, KS 67278-2228

Name of Party Responsible for Plugging Fees: C & S Oil, Robert Christenson

State of Kansas County, Woodson, ss.

Robert Christenson (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) PO box 41, Neosho Falls, KS 66758

SUBSCRIBED and SWORN TO before me this 6th day of May, 2006 Patricia J. Schuster My Commission Expires: December 31st, 2009