

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-19005-00-00
Spot: NENWSW Sec/Twnshp/Rge: 13-16S-9E
2495 feet from S Section Line, 4401 feet from E Section Line
Lease Name: WILLIAMS Well #: 1
County: MORRIS Total Vertical Depth: 2937 feet

KCC
5/15/06
PKT PRT
PMT

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL STREET PO BOX 5
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2918		100 (425 SX ON SQ.)
SURF	8.625	158		124 SX CMT

\$ 95.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/03/2006 9:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: JEFF HAWES Company: GLACIER PETROLEUM CO., INC. Phone: (620) 342-1148

Proposed Plugging Method: Bottom was sanded to 2900' and capped with 4 sacks of cement and pipe was perforated at 200' several years ago. Backside was squeezed with cement up to 60'. Fill casing with cement from 200' to surface. Fill backside of casing to surface with cement.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 05/03/2006 1:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Ran 1" tubing down the backside of 5-1/2" casing to 65'. Well was squeezed with cement below 65'. Pumped 20 sacks of cement to fill to surface. Pulled tubing and ran it inside the casing to 210' and pumped 30 sacks to fill to surface.

50 sacks total of 60/40 posmix with 4% gel

Consolidated #9870

Perfs:

Top	Bot	Thru	Comments
2931	2937		

RECEIVED
KCC DISTRICT #2
MAY - 4 2006
WICHITA, KS

RECEIVED
MAY 15 2006
KCC WICHITA

Remarks: PLUGGED THROUGH 1" HYDRIL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
DATE 5-15-06
NO. 2006061647

PKT