

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20062-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 5-7S-16E  
580 feet from N Section Line, 2070 feet from E Section Line  
Lease Name: KATHRENS Well #: 31-5  
County: JACKSON Total Vertical Depth: 2118 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2080		350 SX CMT
SURF	8.625	218		164 SX CMT

\$ 68.84

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2039' TO 1964', CEMENT FROM 1964' TO 1746', GEL FROM 1746' TO 250', CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 02/14/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2021'. Pumped 9.5 barrels of gel from 2021' to 1964'. Pulled tubing to 1959' and pumped 36 barrels of gel and 25 sacks of cement with 1 sack of cotton seed hulls. Cement was placed from 1959' to 1746' and had gel from 1746' to 250'. Pulled tubing to 251' and circulated 30 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1911	1914		
1883	1886		
1858	1861		
1836	1838		
1819	1823		
1796	1800		

RECEIVED  
KCC DISTRICT #3  
MAY 9 2006 TCH  
CHANUTE, KS

RECEIVED  
MAY 15 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Taylor Citterman  
(TECHNICIAN)

INVOICED  
DATE 5-15-06  
REV. 2006061648