

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20064-00-00  
Spot: SWSE Sec/Twnshp/Rge: 19-6S-16E  
655 feet from S Section Line, 2115 feet from E Section Line  
Lease Name: BROCK Well #: 34-19  
County: JACKSON Total Vertical Depth: 2290 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2274		434 SX CMT
SURF	8.625	217		109 SX CMT

\$ 74.43

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2219' TO 2114', CMT FROM 2114' TO 2064', GEL FROM 2064' TO 250', CMT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 02/03/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2219'. Pulled tubing to 2215' and pumped 11.25 barrels of gel, had gel from 2215' to 2114'. Pulled tubing to 2115' and pumped 39 barrels of gel and 25 sacks of cement with 1 sack of cotton seed hulls. The gel was placed from 2115' to 1897' and cement was from 1897' to 250'. Pulled tubing to 251' and circulated 30 sacks of cement to surface.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 9 2006 TCH

CHANUTE, KS

RECEIVED  
MAY 15 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*Taylor Herman*

(TECHNICIAN)

INVOICED  
STATE 5-15-06  
REV. NO. 2006061648