

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-085-20069-00-00  
Spot: SENV Sec/Twnshp/Rge: 35-5S-16E  
2045 feet from N Section Line, 1945 feet from W Section Line  
Lease Name: SCHRADER-MASSIER Well #: 22-35  
County: JACKSON Total Vertical Depth: 2270 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2255		410 SX CMT
SURF	8.625	217		108 SX CMT

\$ 73.78

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed  
Plugging  
Method:

CEMENT FROM 2208' TO 2158', GEL FROM 2158' TO 250', CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE  
Date/Time Plugging Completed: 02/14/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2208' and pumped 43 barrels of gel and 15 sacks of cement. Cement was placed from 2208' to 2077' and gel from 2077' to 250'. Pulled tubing to 251' and circulated 30 sacks of cement to surface.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAY 9 2006 TCH

CHANUTE, KS

RECEIVED  
MAY 15 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE 5-15-06

PL NO. 2006061648