

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-22507-00-00  
Spot: NENESW Sec/Twnshp/Rge: 29-34S-36W  
2310 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: PARKER ESTATE Well #: 2  
County: STEVENS Total Vertical Depth: 1758 feet

Operator License No.: 5363

Op Name: BEREXCO, INC.

Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	40		
SURF	8.625	1216	0	NOT CMTD/LOST IN HOLE

\$ 57.14

Well Type: LH

UIC Docket No:

Date/Time to Plug: 04/30/2006 5:00 AM

Plug Co. License No.: 5147

Plug Co. Name: BEREDCO, INC.

Proposal Revd. from: GREG KLAUS

Company: BEREXCO

Phone: (316) 265-3311

Proposed Plugging Method: 1ST PLUG AT 560' WITH 100 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 04/30/2006 12:00 AM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

Perfs:

8 5/8" CASING WAS LANDED AT APPROX. 1750' WHEN IT PARTED. TOP OF FISH WAS AT 580'. CASING PARTED 2 TIMES AND WAS LAYING NEXT TO WASH-OUT. APPROXIMATELY 1200' OF 8 5/8" CASING WAS LOST IN THE HOLE. 1ST PLUG RUN DRILL PIPE TO 560' & PUMP 100 SX CMT. 2ND PLUG PULL DRILL PIPE TO 280' & PUMP 50 SX CMT. 3RD PLUG PULL DRILL PIPE TO 60' & PUMP 25 SX CMT. 4TH PLUG CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

INVOICED

DATE 5-15-06  
WEL. NO. 2006061644


RECEIVED  
MAY 15 2006

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed

Jim Holland PIRTA  
(TECHNICIAN)

Form CP 2

PTA