

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-169-20203-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 22-16S-3W  
5023 feet from S Section Line, 3652 feet from E Section Line  
Lease Name: PIHL Well #: 1  
County: SALINE Total Vertical Depth: 3560 feet

Operator License No.: 31934  
Op Name: CASEBEER, INC.  
Address: 909 N. HIGH DRIVE  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3540		180 SX CMT
SURF	8.625	348		225 SX CMT

\$ 115.70

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2006 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

Sand 50' above perfs & cap w/ 4 sxs cmt. Pull pupe and set bridge @ 400'. Dump slurry mix to fill from 400' to surf.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 3210' and capped with 4 sacks of cement. Pulled pipe and set bridge at 400'.  
Dumped 8 yds of slurry mix to fill from 400' to surface.

McPherson Concrete #M35603

8 yds total slurry mix -- 22 sx/yd with 10% sand

Perfs:

Top	Bot	Thru	Comments
3336	3346		

**RECEIVED  
KCC DISTRICT #2  
APR 28 2006  
WICHITA, KS**

**RECEIVED  
MAY 15 2006  
KCC WICHITA**

Remarks:

Plugged through: CSG

District: 02

Signed

Greg Eves

(TECHNICIAN)

**INVOICED**  
DATE 5-15-06  
AMOUNT 2006061645

PKT