

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-03328-00-01  
Spot: NESENW Sec/Twnshp/Rge: 13-10S-20W  
1665 feet from N Section Line, 2365 feet from W Section Line  
Lease Name: SUTOR Well #: 3  
County: ROOKS Total Vertical Depth: 1700 feet

Operator License No.: 32705  
Op Name: RANEY OIL COMPANY, LLC  
Address: 3425 TAM O'SHANTER  
LAWRENCE, KS 66047

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	310	0	w/unknown sxs cmt

\$ 55.25

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2006 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: J.R. HASELHORST Company: RANEY OIL COMPANY, LLC Phone: (785) 749-0672

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Drilled out to 1700' with bit - circulated hole with drilling mud.  
Pulled bit and collars - ran tubing to 1697' to plug well.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/11/2006 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

1st. Plug at 1697' w/25 sxs.  
2nd. Plug at 1000' w/100 sxs.  
3rd. Plug at 360' w/40 sxs.  
4th. Plug at 40' w/10 sxs.

Remarks: SWIFT SERVICES, INC. AND KELLER TANK SERVICE.

Plugged through: TBG

District: 04

**INVOICED**

Signed

Richard Williams BOB

(TECHNICIAN)

5-15-06  
2006061652  
**RECEIVED**

Form CP-2/3

MAY 11 2006

MAY 15 2006  
KCC WICHITA

PKT

PETROLEUM, INC.

#3 SUTOR

13-10-20W  
NE SE NW

Contr.

ROOKS

County

E 222 1/2 RB Comm

Comp. 6-30-50

IP D & A

Tops	Depth	Datum
ANK		
HEEB	3443	-1219
LANS	3482	-1258
CONG	3756	-1532
SIMP	3781	-1557
ARB	3789	-1565
T.D.	3807	-1583

Casing  
 8" 314 ACID 500  
 5" 3790

BERLAND POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MAJICER