

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20096-00-01  
Spot: N2S2NW Sec/Twnshp/Rge: 34-16S-10W  
3910 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: SCHROEDER C OWWO Well #: 7  
County: ELLSWORTH Total Vertical Depth: 3396 feet

Operator License No.: 30364  
Op Name: RESOURCE OPERATIONS, INC.  
Address: BOX 9487  
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3394		150 SX
SURF	9.625	304		275 SX

\$ 110.37

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2006 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TOM ROSE Company: RESOURCE OPERATIONS, INC. Phone: (620) 938-2982

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/25/2006 12:30 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Casing parted at 1570' according to cement bond log by Log Tech of KS on 4/21/2006.  
Perforated at 1300', 1000', and 355'. Ran tubing to 1540' and pumped 25 sacks of cement.  
Pulled tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 1000' and pumped 35 sacks of cement. Pulled tubing to 355' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #24261  
Log Tech #4503

**Perfs:**

Top	Bot	Thru	Comments
3268	3271		ARBUCKLE
RECEIVED KCC DISTRICT #2 APR 28 2006 WICHITA, KS			
RECEIVED MAY 15 2006			

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

**INVOICE**  
DATE 5-15-06  
2006061653

B

PKT