

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19339-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 4-26S-4E
3656 feet from S Section Line, 5164 feet from E Section Line
Lease Name: RICE Well #: 2
County: BUTLER Total Vertical Depth: 2627 feet

Operator License No.: 31878

Op Name: SNYDER, JIM

Address: PO BOX 66
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2624	389	
SURF	8.625	61		

\$ 85.38

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/20/2006 10:00 AM

Plug Co. License No.: 32147

Plug Co. Name: K.E. SNYDER CO., LLC

2/24/06 5:00pm

Proposal Rcvd. from: JOEL SNYDER

Company: K.E. SNYDER CO., LLC

Phone: (620) 344-6083

Proposed Plugging Method: See actual report.

KCC
5-15-06
PKT
per
RBDMS
CP#3
notes

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 02/24/2006 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

2/1/2006 -- RIH with tubing at 2400'. Spotted 25 sacks of class A with 2% cc. Tagged cement at 2298'.

2/3/2006 -- Shot 7" casing at 389'. POOH with 7" casing and 61' of 8-5/8" casing.

2/9/2006 -- RIH with tubing at 250'. Snyder mixed and pumped 125 sacks of 60/40 posmix with 4% gel.

2/15/2006 -- Tagged cement at 160'. RIH with tubing at 158'. Pumped 145 sacks of 60/40 posmix with 4% gel.

2/16/2006 -- Tagged cement at 55'.

2/24/2006 -- RIH with tubing at 50' Snyder mixed and pumped 90 sacks of 60/40 posmix with 4% gel to surface. Ran 1 joint 7" casing to mark well.

Snyder #06-002

Total 360 sxs on top plug

RECEIVED
KCC DISTRICT #2
MAY - 9 2006
WICHITA, KS

RECEIVED
MAY 15 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

INVOICED

DATE 5-15-06

INV. NO. 2006061654

Form CP-2/3

JK

PKT