

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19474-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 4-26S-4E  
4981 feet from S Section Line, 5151 feet from E Section Line  
Lease Name: RICE Well #: 5  
County: BUTLER Total Vertical Depth: 2504 feet

Operator License No.: 31878

Op Name: SNYDER, JIM

Address: PO BOX 66  
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2441	431	
SURF	8.625	120	0	

\$ 81.38

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/26/2006 8:00 AM

Plug Co. License No.: 32147

Plug Co. Name: K.E. SNYDER CO., LLC

Proposal Revd. from: JOEL SNYDER

Company: K.E. SNYDER CO., LLC

Phone: (620) 344-6083

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/27/2006 3:15 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

1/26/2006 -- RIH with tubing at 2350'. Spotted 25 sacks of class A cement. Tagged cement at 2185'.

1/27/2006 -- Shot 5-1/2" casing at 431'. POOH with 6 joints 5-1/2" casing (180'). 5-1/2" casing at 251'. Snyder mixed and pumped 103 sacks of 60/40 posmix with 4% gel to surface. POOH with 254' of 5-1/2" casing. Topped cement back off. Plug down at 3:15 pm.

1/30/2006 -- Tagged cement at 48' from surface. Topped off to surface.

Snyder #06-001

RECEIVED  
KCC DISTRICT #2  
MAY - 9 2006  
WICHITA, KS

Remarks:

Plugged through: CSG

RECEIVED  
MAY 15 2006  
KCC WICHITA

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

INVOICED

DATE 5-15-06

INV. NO. 2006061654

Form CP-2/3

PKT