

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21924-00-00
Spot: W2SWNE Sec/Twnshp/Rge: 31-19S-28W
1980 feet from N Section Line, 2310 feet from E Section Line
Lease Name: SCHMISSEUR FARMS A Well #: 1-31
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	290		WITH 190 SX CMT

152.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/03/2006 7:00 AM

Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: GARY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2200' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: NONE

Date/Time Plugging Completed: 05/03/2006 9:00 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

1ST PLUG AT 2200' WITH 50 SX CMT. 2ND PLUG AT 1350' WITH 80 SX CMT. 3RD PLUG AT 700' WITH 50 SX CMT. 4TH PLUG 330' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.


INVOICED
DATE 5-15-06
INV NO. 2006061655

RECEIVED
MAY 15 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

Form *CF*

PKT