

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19557-00-00
Spot: SENWSW Sec/Twnshp/Rge: 9-25S-5E
1392 feet from S Section Line, 4032 feet from E Section Line
Lease Name: WILSON A Well #: 260
County: BUTLER Total Vertical Depth: 2526 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 6.625 | 2521 | | |
| SURF | 10.75 | 87 | | |

\$ 82.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/26/2006 2:00 PM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/27/2006 10:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4/26/2006 -- Tubing hung up in hole. Shot tubing at 2125'. POOH 2'. United mixed and pumped 50 sacks of class A with 3% cc. Tagged cement at 2095'. Shot holes at 260'. Established circulation. United mixed and pumped 175 sacks of 60/40 posmix with 4% gel to surface. Cement did not circulate between 7" and 10-3/4".

4/27/2006 -- Tagged cement inside tubing at 35'. RIH with 1" at 32'. Filled tubing to surface with cement. Tagged cement between tubing and 7" at surface. United mixed and pumped 200 sacks of 60/40 posmix with 4% gel between 7" and 10-3/4" at 250 lbs.

United #6959 & #6960

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2423 | 2426 | | |
| 2411 | 2416 | | |

RECEIVED
KCC DISTRICT #2
MAY - 9 2006
WICHITA, KS

RECEIVED
MAY 15 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane R. Krueger

(TECHNICIAN)

INVOICED

DATE 5-15-06
NO. 2006061656

A

PK