

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00421-00-02
Spot: SWSWSE Sec/Twnshp/Rge: 21-11S-22W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SPRING VALLEY ANGUS RAN Well #: 2
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	12.25	290		
PROD	4.5	4020	0	300 SX
SURF	8.625	1031	0	w/unknown sxs cmt

\$130.65

Well Type: SWD UIC Docket No: D19876.0 Date/Time to Plug: 05/04/2006 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered 200 sxs cement and 300# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/04/2006 3:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfed at 1800' and squeezed with 375 sxs cement.
Tied to 4 1/2" casing and squeezed 75 sxs cement with 150# hulls.
Max. P.S.I. 1200#. S.I.P. 200#.
Annulus full - visual inspection.
Total of 75 sxs SMD and 150# hulls.

Perfs:

Top	Bot	Thru	Comments
1364	1516		

Remarks: STEWART TANK-WATER

Plugged through: CSG

District: 04

Signed

Roger L Moses
(TECHNICIAN)

HD.
INVOICED

DATE 5-17-06
2006061665

MAY 16 2006

RECEIVED
MAY 17 2006
KCC WICHITA

Form CP-2/3

PET


KANSAS OIL CORPORATION
 400 N WOODLAWN, SUITE 2
 WICHITA, KS. 67208

#2 SPRING VALLEY 21-11-22W
 ANGUS RANCH 'OWWO' SW SW SE

CONTR ABERCROMBIE DRILLING CTY TREGO

GEOL _____ FIELD SHAW CREEK EXT (1/8 N)

E 2333 KB_{CM} 12/28/78 ^{CARD}ISSUED 8/11/79 IP D&A/ARB



API NOT ASSIGNED

LOG	TOPS	DEPTH	DATUM
ANH		1785	+ 548
HEEB		3570	-1237
LANS		3610	-1277
SWOPE		3832	-1499
HERT		3853	-1520
PAW		3932	-1599
LTD		3972	-1639
*CONG		3970	-1637
*ARB		4045	-1712
*TD		4078	-1745
*OLD SAMPLE TOPS			

OLD INFO: OPERATOR WAS PHILLIPS PET.
 #1 EUNICE SPD 7/20/44 SET 12" 249
 COMPLETED AS D&A 8/9/44
 POROUS 3700-10 3974-76

NEW INFO: RE-ENTERED 12/28/78, WSH DWN
 SET 4 1/2" @ 4020/300SX, MICT - CO, PF
 3948-53, RE-PF 3948-53, AC 300 GAL, SWB
 NS, P&A

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS