

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25514-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 26-14S-20W  
1510 feet from S Section Line, 1550 feet from W Section Line  
Lease Name: PFANNENSTIEL Well #: 26-1  
County: ELLIS Total Vertical Depth: 4000 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 900 N TYLER ROAD #14  
WICHITA, KS 67212

String Size Depth (ft) Pulled (ft) Comment  
SURF 8.625 217

\$ 130.00

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: ANDY DINKEL Company: MURFIN DRILLING CO., INC. Phone: \_\_\_\_\_

Proposed Plugging Method: 1st plug @ 1350' w/ 25 sacks  
2nd plug @ 720' w/ 100 sacks.  
3rd plug @ 260' w/ 40 sacks.  
4th plug @ 40' w/ wiper plug and 10 sacks.  
Rathole - 15 sacks.  
Mouse hole - 10 sacks.

Plugging Proposal Received By: DAVID WANN WitnessType: NONE  
Date/Time Plugging Completed: 05/14/2006 11:30 PM KCC Agent: DAVID WANN

Actual Plugging Report:

Perfs:

Well reported plugged as above.  
Order 200 sacks 60/40 pozmix w/ 6% gel and 1/4 lb flowcel per sack.

Remarks: CEMENTED BY ALLIED CEMENTING.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 5-17-06

TEL. NO. 2006061666

MAY 16 2006

RECEIVED

MAY 17 2006

KCC WICHITA

Form CP-2/3

PKT