

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21322-00-00
Spot: S2 Sec/Twnshp/Rge: 21-31S-21W
1225 feet from S Section Line, 2540 feet from E Section Line
Lease Name: MOORE Well #: 21-15-4
County: CLARK Total Vertical Depth: 6470 feet

Operator License No.: 33060
Op Name: DIVERSIFIED OPERATING CORP.
Address: 15000 WEST 6TH AVE., SUITE 102
GOLDEN, CO 80401

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5125		WITH 2 SX CMT
COND	20	44		
PROD	4.5	5301	2000	WITH 150 SX CMT
SURF	8.625	673		WITH 450 SX CMT

\$ 210.28

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/11/2006 1:30 PM
Plug Co. License No.: 33645 Plug Co. Name: PLAIN, LLC
Proposal Revd. from: ALAN WALKER Company: DIVERSIFIED OPERATING Phone: (303) 384-9611

Proposed Plugging Method: CIBP @ 5140' WITH 2 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PLUG AT 680' WITH 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/11/2006 3:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 5125' WITH 2 SX CMT. 1ST PLUG AT 1203' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 15 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5167	5176		


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

Plugged through: CSG

DATE 5-18-06
INV. NO. 200606016.71

District: 01



Signed

Jerry W. Stapleton
RECEIVED
(TECHNICIAN)

PART II

MAY 18 2006
KCC WICHITA

PCT AMSE