

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10901-00-01
Spot: NESESE Sec/Twnshp/Rge: 10-26S-14W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: HENDERSON B Well #: 1
County: PRATT Total Vertical Depth: 4302 feet

Operator License No.: 32619
Op Name: EXCEL OIL & GAS L.L.C.
Address: PO BOX 68
BUCYRUS, KS 66013

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4302	1440	WITH 625 SX CMT
SURF	8.625	889		WITH 400 SX CMT

\$ 139.82

Well Type: EOR UIC Docket No: E19437.1 Date/Time to Plug: 05/12/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND OFF TO 4170' WITH 5 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/12/2006 10:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BACK TO 3180' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 900' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4222	4227		


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND.

DATE 5-18-06
WV. NO. 2006061672

Plugged through: CSG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAY 18 2006
KCC WICHITA

PLT RWB