

15-163-03167-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Cities Service Oil Co. Address Bartlesville, Oklahoma
(Applicant)

Lease (Farm Name) Adams "B" Well No. 3

Well Location NE NE of S/2 ^{CS/2} NE NE Sec. 33 Twp. 8 Rge. (E) - (W) 16

County Rooks Field Name (if any) Laton

PBTD 3242'
Total Depth 3265 Oil Gas Dry Hole

Was well log filed with application? yes If not, explain: attached

Date and hour plugging is desired to begin as soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner J. W. Young, c/o

Address Cities Service Oil Co., Box 515
Plainville, Kansas

Plugging Contractor no contractor

Plugging Contractor's License No. _____

Address _____

Invoice covering assessment for plugging this well should be sent to _____

James Porter, Cities Service Oil Co. Address Box 553, Russell, Kansas.

and payment will be guaranteed by applicant.

James Porter ^{5/27/55}
Applicant or Acting Agent

Date May 25, 1955

PLUGGING
FILE SEC 33 T 8 R 16W
BOOK PAGE 122 LINE 32

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1955
CONSERVATION DIVISION
WICHITA, KANSAS

15-163-03167-00-00



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
~~100-1000000000000000~~
WICHITA 2, KANSAS

211 N. Broadway

May 27, 1955

Well No.	3
Lease	Adams #17
Description	CS/2 NE NE 33-8-16W
County	Hooks
File No.	122-37

Cities Service Oil Co.
Box 553
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: District Plugging Supervisor

Company: Cities Service Oil Co. Well No. 3 Farm: Adams "B"
 Location: 990' South and 710' West of NE Corner Sec. 33-T. 8-R.-16W
 Elevation: 1903 (1901) County: Rooks State: Kansas
 Drlg. Comm. December 1, 1949 Contractor: Lohmann-Johnson Drlg. Co., Inc.
 Drlg. Comp. December 12, 1949 Acid: 5,000 gals. (see below)
 T.D. 3265' Initial Prod: pumped 14 oil, 6 water, 24 hrs. (2-10-50)
 PBTD 3242'

Casing Record:
 8-5/8" @ 305' cem. 150 sx cement
 4-1/2" @ 3265' cem. 175 sx cement

Top Heebner 2975'
 Top Dodge 2996'
 Top Lansing 3016'
 Penetration 249'
 Total Depth 3265'

FORMATION RECORD:

shale and shells 0-306
 sand and shale 627
 shale and iron 663
 shale and shells 739
 sand 850
 shale and shells 1130
 shale 1170
 anhydrite 1205
 shale and shells 1268
 shale 1557
 shale and lime 1740
 shale and shells 1915
 broken lime 1983
 lime 2114
 lime and shale 2175
 lime 2180
 shale and shells 2267
 shale and lime 2445
 broken lime 2520
 shale and lime 2603
 broken lime 2684
 lime and shale 2780
 lime 2840
 lime and shale 2873
 lime 3265

Drilled cement to 3242' SLM.

Perf. 31 shots 3227-3236'
 Perf. 30 shots 3180-88'
 Perf. 31 shots 3082-90'
 Perf. 19 shots 3073-78'
 Perf. 54 shots 3054-68'
 Perf. 24 shots 3035-41'
 Perf. 24 shots 3023-29'
 Perf. 24 shots 3014-20'
 Perf. 22 shots 2993-99'

Acidizing Record 12/19/49.
 750 gals. 3227-36'
 750 gals. 3180-88'
 2000 gals. 3054-90'
 1000 gals. 3014-41'
 500 gals. 2993-99'

SLOPE TESTS (ACID BOTTLE):
 500' OK
 1000' OK
 1500' OK
 2000' OK
 2500' OK
 3000' OK

3265 RTD = 3265 SLM

7-7/8" Rotary Hole.

5/27/55

RECEIVED
 STATE CORPORATION COMMISSION

MAY 27 1955

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 33 T 8 R 16W
 BOOK PAGE 122 LINE 37