

15-063-01333-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Cities Service Oil Co. Address Bartlesville, Oklahoma
(Applicant)

Lease (Farm Name) Adams "C" Well No. 1

Well Location 990'S 990'E of center Sec. 33 Twp. 8 Rge. (E) - (W) 16

County Rooks Field Name (if any) Laton

PBTD 3165'

Total Depth 3295' Oil Gas Dry Hole

Was well log filed with application? yes If not, explain: attached

Date and hour plugging is desired to begin as soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner J. W. Young

Address c/o Cities Service Oil Co., Box 515
Plainville, Kansas

Plugging Contractor no contractor

Plugging Contractor's License No. _____

Address _____

Invoice covering assessment for plugging this well should be sent to _____

James Porter, Cities Service Oil Co. Address Box 553, Russell, Kansas.

and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION

James Porter
Applicant or Acting Agent

Date May 25, 1955

PLUGGING
FILE SEC 33 T 8 R 16W
BOOK PAGE 122 LINE 38

3/27/55

15163-81333-00-00



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
~~UNDESIGNATED~~
WICHITA 2, KANSAS

211 N. Broadway

May 27, 1955

Well No.	1
Lease	Adams #00
Description	NE NW SE 33-8-16W
County	Rooks
File No.	122-38

Cities Service Oil Co.
Box 553
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: District Plugging Supervisor

15-143-01333-00-00
WELL RECORD

Company: Cities Service Oil Co. Well No.: 1 Farm: Adams "C"

Location: 990' South and 990' East of Center Sec. 33, T. 8, R. 16W

Elevation: 1951' (1949) County: Rooks State: Kansas

Drlg. Comm. 6/15/47 Contractor: Holm Drilling Co.

Drlg. Comp. 6/26/47 Acid: 1000 gal. 3068-73', 2000 gal 3095-3116, 2000 gal 3128-52 7/30/47

T.D. 3295'; PBSD 3165' Initial Prod. Swab 32 oil, 18 water, 24 hrs. 8/3/47.

Casing Record:

8-5/8" @ 220' w/125 sx. cement
4 1/2" @ 3295' w/125 sx. cement

Corr. Top Lansing 3068'
Penetration 227'
Total Depth 3295'

Formation Record:

Clay and shells	0-40
Shale and shells	435
Sand and shells	455
Shale and shells	510
Sand and shale	765
Shale and lime	830
Sandy shale	870
Sand	940
Red shale and shells	1228
Anhydrite	1258
Shale and shells	1675
salt, shale, shells	1725
Lime and shale	1880
Shale	1915
Lime and shale	2280
Lime	2310
Lime and shale	2550
Shale and shells	2605
Lime and shale	2745
Shale and shells	2835
Lime	2900
Lime and shale	2945
Lime	2970
Lime and shale	2999
Lime	3104
Lime and shale	3120
Lime broken	3131
Lime soft	3136
Lime broken	3147
Lime	3250
Lime broken	3275
Shale	3290
Lime	3295 T.D.

Drilled cement to 3278 1/2 S.L.M.

Perf. 27 shots 3260-68 show oil.
Perf. 18 shots 3227-32
Perf. 34 shots 3172-82: 350' water in 3 hrs.

Set Lane-Wells plug 3165-68'.

Perf. 31 shots 3144-52
Perf. 24 hots 3128-33
Perf. 38 shots 3106-16
Perf. 15 shots 3095-3101
Perf. 8 shots 3068-73

16 gallons water and 2 gallons oil per hours.

SYFO:
500' 0°
1000' 0°
1500' 0°
2000' 0°
2500' 0°
2970' 0°

7-7/8" Rotary Hole.

10/17/51 Plugged back to 3035' with 8 1/2 sx. cement. T.A.

PLUGGING
FILE SEC 33 T. 8 R. 16W
BOOK PAGE 122 LINE 38

RECEIVED
STATE CORPORATION
MAY 27 1955
CONSERVATION DIVISION
Wichita, Kansas
S/27/55