

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

15-163-21715-00-00

API NUMBER 15-163-21715

LEASE NAME Stamper

WELL NUMBER 1-5

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 5 TWP. 8S RGE. 17W (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 12-15-93

Plugging Completed 12-16-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graham-Michaelis Corp.

ADDRESS P. O. Box 232, Russell, KS 67665

PHONE# (316) 483-3136 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3375'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	254'	none
				4 1/2	3375'	700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set Sanded bottom @ 3010 & 4 sks cement. Shot @ 1700, 1300 & worked pipe. Spotted 100 sks cement & 200# hulls @ 950. SHot @ 900 & 700, came loose. Pulled to 660, spotted 50 sks. Pulled to 400, spotted 50 sks & circulated to surface. Pulled rest of pipe, topped off w/10 sks. 60/40 pos 10% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P. O. BOX 347 CHASE, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF KANSAS COUNTY OF RICE, ss. STATE CORPORATION COMMISSION

R. DARRELL KELSO

(Employee of Operator) JAN 03 1994 (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P. O. BOX 347 CHASE, KS 67524

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 93

Irene Herzberg
Notary Public

My Commission Expires: _____

