


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-163-02983-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rooks \_\_\_\_\_ County. Sec. 5 Twp. 8 Rge. 17 (E) (W)  
Location as "NE/CNW%SW%" or footage from lines. SE NE SE  
Lease Owner Okmar Oil Company  
Lease Name Eckart Well No. 2  
Office Address 1130 Wichita Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed November 1952  
Application for plugging filed July 1961  
Application for plugging approved July 1961  
Plugging commenced July 5, 1961  
Plugging completed August 9 1961  
Reason for abandonment of well or producing formation Oil depleted

If a producing well is abandoned, date of last production September 1960  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top 3385' Bottom 3391' Total Depth of Well 3391 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	108'	0
				5 1/2"	3386'	1007'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 3090' run 20' sand and 5 sacks cement from 3090' to 3040' had 8 5/8" cut off, working 6" tension in 5 1/2", shot at 2780' and spotted oil. Working 6" tension in 5 1/2" pipe. Shot at 2560', 2004', 1506', 1240' 1004' and started 5 1/2" pipe, pumped 5 sacks of gel mud at 500' and 20 sacks of cement, pumped 20 sacks of cement at 170' and run 10 sacks to base of collar.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Company  
Address Box 114, Ellinwood, Kansas

5-20-64

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Robert M. Beren

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Robert M. Beren  
1130 Wichita Plaza, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 64.

My commission expires March 12, 1966

Jeannine Requa  
Notary Public.

