

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-1 63-21,541 00-00

LEASE NAME Stamper "A"

WELL NUMBER 1

SPOT LOCATION SE SE NE

SEC. 5 TWP. 8S RGE. 17 (E or W)

COUNTY Rooks

Date Well Completed 2-9-82

Plugging Commenced 3-8-85

Plugging Completed 3-8-85

LEASE OPERATOR Graham-Michaelis Corporation

ADDRESS P. O. Box 247, Wichita, Kansas 67202

PHONE # (316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Dennis Hammel

Which KCC/KDHE Joint Office did you notify? Plainville, Kansas - District 6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Arbuckle Depth to top 3330 bottom 3450 T.D. 3450

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle				5-1/2"	3448'	None
				8-5/8"	270'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

See attached sheet.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this form.)

MAR 20 1985
3/20/85

Name of Plugging Contractor Graham-Michaelis Corporation

CONSERVATION DIVISION
License No. 5134
Wichita, Kansas

Address P. O. Box 247, Wichita, Kansas 67201

3-13-85
RECEIVED

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

Jack L. Yinger (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAR 13 1985

(Signature) Jack L. Yinger
(Address) P. O. Box 247, Wichita, KS 67201

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 12 day of March, 1985

ALDINE M. JOHNSON
NOTARY PUBLIC

My Commission expires:

STATE OF KANSAS
My Appointment Expires:
3-19-85

Notary Public

Form CP-4 1-84
Revised 06-83

Graham-Michaelis Corporation
Stamper "A" #1
SE SE NE Sec. 5-8S-17W
Rooks County, Kansas

15-163-21541-00-00

The Stamper "A" #1 was plugged in the following manner:

The Dakota water broke in at a depth of 750 to 755'. We immediately pulled tubing and rods and squeezed the hole in the casing at 750 to 755' with 350 sacks cement. Cement circulated to surface between the 5-1/2" production casing and the 8-5/8" surface casing. We drilled out cement and at 759' we started drilling on casing. We went in hole with a milling shoe and milled from 759 to 764' and in shale and cement from 764 to 775'. Came out of hole with wash pipe and milling shoe. Went in hole with bit and drilled down and concluded we were outside the 5-1/2" production casing and, in fact, the production casing had parted at approximately 755' and had kicked over in the hole.

Dennis Hammel, Plainville, KS

We continued down the side of the casing to 1020' and called State Plugger / and received plugging instructions. There was good circulation and we mixed 25 sacks of cement and filled the drill pipe. Pulled up one joint and again refilled the casing with cement and attempted to pull out another joint of casing. At that point the pipe stuck in the hole. We ran a Dia-Log free-point and backed off pipe at 759'. We left 5 drill collars and 1 joint of tubing in the hole. We then came out of hole and went back in and set a packer at 606' and cemented with 200 sacks of cement at 1200#. Then filled 5-1/2" casing with 75 sacks of cement to surface. Job complete.

JLY:aj

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1985
326-85
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1985
CONSERVATION DIVISION
Wichita, Kansas