

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,229

LEASE NAME BEMIS -00-07

WELL NUMBER #2 SWD

SPOT LOCATION NE NW SW

SEC. 5 TWP. 8 RGE. 17 (E) or (W)

COUNTY ROOKS

Date Well Completed 1-12-84

Plugging Commenced 3-15-89

Plugging Completed 3-30-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ROSEL ENERGY, INC.

ADDRESS P.O. Box 1068 LIBERAL, KANS. 67901

PHONE # (316) 624-4994 OPERATORS LICENSE NO. 5941

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? #4 HAYS

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing formation ARBUCKLE Depth to top 3371' bottom 3500' T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>ARBUCKLE</u>				<u>8 7/8"</u>	<u>762'</u>	<u>NONE</u>
				<u>5 1/2"</u>	<u>3371'</u>	<u>NONE</u>
				<u>2 7/8"</u>	<u>898</u>	<u>250' LEFT 600' IN HOLE.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 3-15-89 RAN WIRELINE, T.D. @ 818', HOLE IN 5 1/2" @ 760', PUMP 30 BBLs CEMENT DOWN 8 7/8, SHUT IN FOR A WEEK. 3-29-89 8 7/8 ON VAC. 5 1/2 FLOWING. T.D. 766. ATTEMPT TO DRILL TO ANHYDRATES PER STATES ORDERS. COULD NOT DRILL PAST 756' (BAD PIPE) STATE SAID Plug THERE. RUN 2 7/8 TO 892 & SPOT 100 SX. COMMON. GOT T&G STRUCK. HAD TO BACK-OFF. LEFT 600' T&G IN HOLE. SPOT 50 SX DOWN 8 JTS T&G THAT WE GOT FREE THEN BUMPED 50 SX DOWN 5 1/2 CSG. AND 50 SX DOWN 8 7/8 SHUT IN. OVER PLEASE.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ROSEL ENERGY, INC. License No. 5941

Address P.O. Box 1068 LIBERAL, KANSAS 67901

STATE OF Kansas COUNTY OF Seward

Doris M. Gibson, Corp Sec. (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true
correct, so help me God.


(Signature) Doris M. Gibson

(Address) P.O. Box 1068, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1989

Rhonda L. Bohannan
Notary Public

My Commission expires: June 10, 1990



RECEIVED
STATE CORPORATION COMMISSION
JUN 13 1989
6/13/89

ON APPROX 4-10 HAD WELL HEAD CUT OFF.

CEMENT WAS 2' BELOW GROUND LEVEL IN 5/8" CSS.

CEMENT WAS @ THE SURF. IN THE 8 5/8" SURF. PIPE.

STATE MAN WAS ON LOCATION THRU ENTIRE PLUGGING OPERATION.