

15-163-00511-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 6 Twp. 8 Rge. 17 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Murfin Drilling Co.

Lease Name GOLDIE Well No. 1

Office Address 910 Union Natl. Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-25-53 19

Application for plugging filed 3-24-53 19

Application for plugging approved 3-24-53 19


Plugging commenced 3-25-53 19

Plugging completed 3-25-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 3345 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	128'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sun Cementing Co. - filled with 50 sks. Portland cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company,

Address 910 Union National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. W. R. Murfin

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.R. Murfin (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of April, 1953

My commission expires 6-4-55

STATE CORPORATION COMMISSION Abby Weimerman Notary Public.

24-2675-5 2-52-20M

CONSERVATION DIVISION

4-30-53

PLUGGING
WELL SEC 6 T 8 R 17 W
BOOK PAGE 89 LINE 27

WELL LOG

15-163-00511-00-00

Company: Murfin Drilling Company

NE NE NE
Section 6-8-17W
Rooks County, Kansas

Farm: GOLDIE #1

Elevation: 1864' RB

Total Depth: 3345'

Commenced: 3-13-53

Production: D & A

Completed: 3-25-53

Contractor: Murfin Drilling Co.

Casing: 8 5/8" - 128' w/90 sacks cement

Formations:

Tops:

500'	Shale	Cimarron Anhydrite	1239' (-625)
520'	Sand	Topeka	2772' (-908)
545'	Sand & Iron	Heebner	2986' (-1122)
725'	Shale & Shells	Toronto	3009' (-1145)
970'	Sand	Lansing - K.C.	3028' (-1164)
1145'	Red Bed	Base K. C.	3246' (-1382)
1239'	Red Bed & Shale	Arbuckle - rework	3324' (-1460)
1271'	Anhydrite	Arbuckle - dolomite	3331' (-1467)
1330'	Shale		
1730'	Shale, Shells & Iron	D. S. T. #1 - 3052-3077 - open 1 hr - weak steady blow 5 minutes. Rec'd 20' watery mud w/trace of oil. B.H.P. 990 psi. in 15 min.	
2455'	Shale & Lime		
2560'	Shale, Lime & Shells	D. S. T. #2 - 3120-3135, open 1 hr - strong blow dim. at end of test. Rec'd 795' s.w. B.H.P. 1125 psi in 20 min. I.F.P. 50# F.F.P. 400#	
2680'	Shale		
2775'	Shale & Lime		
2840'	Broken Lime		
3010'	Lime & Shale		
3345'	Lime		
3345'	TDR		

RECEIVED
STATE CORPORATION
APR 30 1953
CONSERVATION DEPARTMENT
Wichita, Kansas

4-30-53

State of Kansas)
County of Sedgwick) ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of

the GOLDIE #1 well.

W. R. Murfin

Subscribed and sworn to before me this 29th day of April 1953.

Abby Heimerman
Notary Public

My Commission Expires: 6-4-55

PLUGGING
FILE SEC 6 T 8 R 17W
BOOK PAGE 89 LINE 27