


15-163-20519-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 6 Twp. 8S Rge. 17W (E) _____ (W)^X
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Clinton Oil Company
Lease Name W.H. Brown Well No. 1-V
Office Address 217 North Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed _____ 19 74
Application for plugging filed _____ 19 74
Application for plugging approved _____ 19 74
Plugging commenced _____ 19 74
Plugging completed _____ 19 74
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3420 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	239'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 600' w/70 sx cmt;
Plug @ 215' w/20 sx cmt;
Plug @ 40' w/10 sx cmt.

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Red Tiger Drilling Company (If additional description is necessary, use BACK of this sheet)
Address 1720 Wichita Plaza, Wichita, Kansas 67202 3-15-74


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of March, 19 74

October 25, 1976

Gloria Sawcett
Notary Public.



15-163-20915-00-00

DRILLERS LOG

No. 1-V W.H. Brown

CASING RECORD:

8-5/8" @ 239'
w/200 sx cmt

TOTAL DEPTH: 3420'

COMPANY: Clinton Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: February 25, 1974

COMPLETED: March 7, 1974

DESCRIPTION:

SW SE SW
6-8S-17W
Rooks County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Post Rock & Shale	0	480
Shale	480	795
Sand	795	985
Shale	985	1281
Anhydrite	1281	1316
Shale	1316	1950
Shale & Lime	1950	2130
Lime	2130	2245
Shale & Lime	2245	2865
Lime	2865	3320
Lime & Shale	3320	3360
Lime	3360	3420

REMARKS

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1974
CONSERVATION DIVISION
Wichita, Kansas
3-15-74

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 12th day of March, 1974.



Gloria Fawcett
Notary Public

Commission Expires:
October 25, 1976