

15-163-20048-00-00

SP

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County. Sec. 7 Twp. 8 Rge. 17 (X) W (W)

Location as "NE/CNW/SW" or footage from lines NE SW SW

Lease Owner C-G DRILLING CO.

Lease Name HRABE A #2

Office Address 107 RULE BUILDING, WICHITA, KANSAS 67202 Well No.

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed AUGUST 8, 1967 19

Application for plugging filed AUGUST 8, 1967 19

Application for plugging approved AUGUST 8, 1967 19

Plugging commenced AUGUST 8, 1967 19

Plugging completed AUGUST 8, 1967 19

Reason for abandonment of well or producing formation TOO LOW STRUCTURALLY

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO F MASSEY, HAYS, KANSAS 67601

Producing formation Depth to top Bottom Total Depth of Well 3406 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202.45'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED WITH HEAVY MUD TO 1040'. SET PLUG.
PUT IN 100 SACKS CEMENT. FILLED WITH HEAVY MUD TO 210'. SET PLUG. PUT IN 20 SACKS.
FILLED WITH HEAVY MUD UP TO 40'. SET PLUG.
FILLED TO TOP WITH 1/2 SACKS HULLS, AND 10 SACKS CEMENT.

RECEIVED
AUG 21 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor C-G DRILLING CO. (If additional description is necessary, use BACK of this sheet)

Address 107 RULE BUILDING, WICHITA, KANSAS

8-21-67

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. G F GALLOWAY

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G F GALLOWAY 107 RULE BUILDING (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of AUGUST, 19 67

My commission expires JAN 23, 1968

Phyllis McJimsey Notary Public.

15-163-20048-00-00

AP

WELL LOG

OPERATOR: C-G DRILLING CO.

WELL NAME: HRABE A #2 LOCATION: NE SW SW 7-8-17W

COUNTY: ROOKS STATE: KANSAS

WELL COMMENCED: 7/31/67 WELL COMPLETED: 8/19/67

ELEVATION: 1946 KB TOTAL DEPTH: 3406'

PRODUCTION: DRY & ABANDONED RIG NO: 1

CASING - 8-5/8": 6 JTS 8-5/8" 202.45' CEM. W/140 QUICKSET

5-1/2": -

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
555	820	SHALE	1/4° 500'	DST #1 3099-3138'
820	1020	SAND	1° 1500'	DST #2 3239-3296'
1020	1160	RED BED	3/4° 2000'	DST #3 3294-3320'
1160	1310	SHALE	3/4° 2500'	DST #4 3318-3340'
1310	1353	ANHYDRITE	3/4° 2900'	DST #5 3383-3396'
1353	1780	RED BED & SHALE	1/2° 3296'	
1780	1990	SHALE & LIME		
1990	2200	LIME & SHALE		
2200	3105	LIME & SHALE		
3105	3396	LIME		
3396	3406	ARBUCKLE		

RECEIVED
 STATE GEOLOGICAL COMMISSION
 AUG 21 1967
 CONSTRUCTION DIVISION
 WILMOTA, KANSAS
 821-67

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature]
 G F GALLOWAY

SUBSCRIBED AND SWORN TO, BEFORE ME, This 18th day of AUGUST, 1967.

My comm. exp: Jan. 23, 1968

[Signature]
 Phyllis McJimsey ---Notary Public