

15-163-79722.00-00
01008

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner R. P. Nixon Address 754 E. Wichita Ave., Russell, Kans.
(Applicant)

Lease (Farm Name) Bay Well No. 1

Well Location SW/SW/SW Sec. 17 Twp. 8 Rge. 17 (E) (W)

County _____ Books _____ Field Name (if any) _____

Total Depth 3355' Oil _____ Gas _____ Dry Hole X

Was well log filed with application? yes If not, explain: _____

Date and hour plugging is desired to begin 9-11-56

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner _____

J. O. Forbes d/b/a Forbes Casing Address Box 221, Great Bend, Kans as

Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company

Plugging Contractor's License No. 49

Address Box 221, Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to _____

R. P. Nixon Address 754 E. Wichita Ave., Russell, Kansas

and payment will be guaranteed by applicant.

J. O. Forbes
Applicant or Acting Agent

SEP 13, 1956

Date 9-11-56

PLUGGING
FILE SEC. 17 T. 8 R. 17 W
BOOK PAGE 98 LINE 27

15-163-19122-00-07
01008



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

September 13, 1956

Well No. 1
Lease Ray
Description SW SW SW 17-8-17E
County Rooks
File No. 98-27

R. F. Nixon
75th S. Wichita Ave.
Russell, Kansas

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

By S. S. Greider
S. S. Greider
WELL PLUGGING SUPERVISOR

cc:
District Plugging Supervisor



Shields

WELL LOG

15-163-19122-00-00

01008

Russell, Kansas

Operator: R. P. Nixon, et al


Well: Ray #1

Commenced: June 18, 1956

Completed: June 27, 1956

Contractor: Shields Drilling Company, Inc.

Well Description: SW SW SW



Sec. 17-8-17W

Rooks County, Kansas

CASING RECORD

Size	Run	Pulled
8 5/8"	200'	Cmtd. with 100 sax
4 1/2"	3355'	Cmtd. with 100 sax

Elevation: 1884' RB

Treatment:

Production:

Tops:

Heebner	3006'
Toronto	3025'
Lansing-K. C.	3048'
Arbuckle	3312'

..... Figures Indicate Bottom of Formations

Surface Soil	25
Shale	510
Sand & Shale	885
Shale & Sand	975
Red Bed	1240
Anhydrite	1270
Shale & Shells	1745
Shale	1870
Shale & Lime	2035
Lime & Shale	2145
Lime Shale Streaks	2295
Shale & Shells	2395
Lime & Shale	2855
Lime Shale Streaks	2935
Lime & Shale	2997
Shale & Lime	3032
Lime	3355 RTD

Sep. 13, 1956

PLUGGING
 FILE SEC 17 T 8 R 17W
 BOOK PAGE 98 LINE 27

Notes

DST #1 3311-22 Tool open 30 min, with weak blow for 15 min. Recovered 20' oil and gas cut mud with approximately 1 gal. free oil. BHP-530#/20 min.