

Operator Name: Rosewood Resources, Inc. Lease Name: Stasser Well #: 1-4
 Sec. 4 Twp. 7 S. R. 38 East West County: Sherman

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No (Attach Additional Sheets) Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (Submit Copy) List All E. Logs Run: Triple Combo, DSI	Log Formation (Top), Depth and Datum Sample Name Top Datum <i>Beecher Island 1032 +2556</i> RECEIVED KANSAS CORPORATION COMMISSION SEP 25 2002 CONSERVATION DIVISION WICHITA, KS
--	---

CASING RECORD New Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	9 7/8"	7"	20	350	Neat	150	3%cc1/4# Flocel
Production	6 1/4 "	4 1/2"	10.5	1211	50/50 Poz.	60	10% salt

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)		Depth
2	1192'-1194'/Set 4 1/2" CIBP @ 1175'	Dump bailed 20' cement on top of CIBP		
2	1031'-1056'	Frac w/ 44646 gal & 74,740# 20/40 sd + 25,000# 12/20 sd + 20 tons CO2		

TUBING RECORD		Size	Set At	Packer At	Liner Run	Yes	No
N/A							
Date of First, Resumed Production, SWD or Enhr.		Producing Method					
<i>SI 02-03-04</i>		<i>See wireline Perforate</i>		<input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbbs.	Gas Mcf	Water Bbbs.	Gas-Oil Ratio	Gravity		
	0	40	0				

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____



CEMENTER'S WELL SERVICE, INC.
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

RECEIVED
 KANSAS CORPORATION COMMISSION No 182410

SEP 25 2002

CONSERVATION DIVISION
 WICHITA, KS

Rosewood

Date	5-07-02	Well Owner	Resources Inc.	Well No.	1-4	Lease	Stassec
County	Sheeppan	State	Kansas			Field	
Charge to	Rosewood Resources Inc.					Charge Code	
Address	P.O. BOX 1668					For Office Use Only	
City, State	Vernal, Utah, 84078						
Pump Truck No.	1204	Code		Bulk Truck No.	1211	Code	
Type of Job		Depth		Ft.	1236'	To	
Surface		Bottom of Surface		Ft.		To	
Plug		Plug Landed @	1211'	Ft.		Time On	19:30 PM
Production	4 1/2" casing 10.5'	Pipe Landed @	1211'	Ft.		Time Off	plug down @ 22:00 PM

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat				4500.00
	Poz. Mix ✓ 50/50	60	SKS		
	Calcium Chloride 10% SALT				
	Gel 2 % Flo-Cele #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	4 1/2" Centralizers	6			
	" Scratchers	7			
	" A.F.V. shoe	1			
	" Latch Down plug & Baffle	1			
	Mixing Rate 4 BPM - Displacement Rate 6 BPM				
	Yield 1.26 CU.FT./SK - Slurry WT 14.2 PPG				

WELL SERVICE
 Stamp 1-4
 ACCOUNT CODE
 1705044
 APPROVAL
 DW
 PAY DATE
 5-23-02

Remarks: Preflush w/ 10 BBLs mud flush
 Displace w/ 19 BBLs KCL
 Landed plug w/ 2000 PSI

Tax Reference Code	Sub Total	4500.00
Rate 4.9 %	Tax	220.50
Disc.	Total	4720.50

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1204		Pump Truck		20		50	
1211		Bulk Truck		20		50	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing subject to review and revision.

Delivered By Leon-Kenny

Received By [Signature]
 Customer or His Agent