

15-163-01819-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

RECEIVED
STATE CORPORATION COMMISSION
DEC 9, 1988
DEC 9 1988

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER _____ (of this well _____) (This must be listed; if no API# was issued, please note drilling completion date.)
CONSERVATION DIVISION Wichita, Kansas 7/89

LEASE OPERATOR T. O. Rush OPERATORS LICENSE NO. 3846

ADDRESS Box 322 Haysville, Ks. 67060 PHONE # () 773-1247

LEASE (FARM) Krug WELL NO. 8 WELL LOCATION _____ COUNTY Rooks

SEC. 19 TWP. 8S RGE. 17W or (W) TOTAL DEPTH 3428 PLUG BACK TO 3370 (Bridge Plug)

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 1319 CEMENTED WITH 600 SACKS
CASING SIZE 5 1/2 SET AT 3409 CEMENTED WITH 150 SACKS
PERFORATED AT Perf. 3129 - 3326 Cement Top 2762

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE 1 jt. Tube 3267' Packer at 3310'

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Sand back to 3100' spot 6 sacks cement, Mud to 1500', run tubing to 1500' circulate cement 5 1/2 to top, Pump 100 sacks between 8 5/8 and 5 1/2

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? N/A IS ACO-1 FILED? unknown
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-8-1988 8:00 A.M.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Tom Rush 773-1247
PHONE # () _____

ADDRESS Box 322 Haysville, Kansas 67060

PLUGGING CONTRACTOR Gressel Corp. LICENSE NO. 5822 6/89

ADDRESS Box 327 Haysville, Ks. 67060 PHONE # () 773-1248

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Gary Stearns (Operator or Agent)

DATE: 12-7-88

4

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH McCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

December 12, 1988

MAR 12 1989

WELL PLUGGING NOTICE

EXPIRES

Krug #8
Sec. 19-08S-17W
Rooks County

T. O. Rush
Box 322
Haysville, KS 67060

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200