

RECEIVED

MAY 23 2006

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA Form must be Signed All blanks must be Filled

Form CP-4 December 2003

Lease Operator: VESS OIL CORPORATION

Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

Phone: (316) 682-1537 Operator License #: 5030

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: May 18, 2006 (Date)

by: Duane Krueger (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Kansas City Depth to Top: 2075 Bottom: 2108 T.D. 2599

Simpson Depth to Top: 2588 Bottom: 2599 T.D.

Depth to Top: Bottom: T.D.

API Number: 15-015-21,375-00-00

Lease Name: Augusta Unit

Well Number: 5-53

Spot Location (QQQQ): 50'S SE NW

2030 3204 Feet from North / South Section Line

1980 3388 Feet from East / West Section Line

Sec. 11 Twp. 28S S. R. 04E East West

County: Butler

Date Well Completed: 4/2/81

Plugging Commenced: 5/18/06

Plugging Completed: 5/19/06

KCC Pkt 5/24/06 Per GPSD Ftg

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Kansas City and Simpson formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

5/18/06: Run tbg to 2050', United Cement spot 50 sx Class A, 3% cc, bottom plug. Pull tbg. Ticket # 7119

5/19/06 Wireline tag btm plug @ 1680'. Shot csg @ 875', wouldn't come. 710': casing free. Pulled it out.

Run 2-3/8" tbg to 310'. United Cement: mix & pump 105 sx 60/40 pozmix, 6% gel. Circ. good. Pull out: top off w/15 sx. Full

Ticket #6967.

Name of Plugging Contractor: United Cementing and Acid Company, Inc. License #: 30437

Address: 2510 W. 6th, El Dorado, KS 67042

Name of Party Responsible for Plugging Fees: Vess Oil Corporation

State of Kansas County, Sedgwick, ss.

Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats

(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 22nd day of May 20 06

Michelle D. Henning Notary Public

My Commission Expires MICHELLE D. HENNING NOTARY PUBLIC STATE OF KANSAS 7/10/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pkt