

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

MAY 19 2006

KCC WICHITA

Form CP-4
December 2003

Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc.

Address: 250 N. Water, Suite 300

Phone: (316) 267-3241 Operator License #: 30606

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Darrel Dipman (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: _____ Bottom: _____ T.D. _____
Toronto Depth to Top: _____ Bottom: _____ T.D. _____
LKC Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-20323-0000

Lease Name: Gano SE Unit

Well Number: 1-4

Spot Location (QQQQ): NW - SW - NW -
3630 Feet from North / South Section Line

4950 Feet from East / West Section Line

Sec. 12 Twp. 10 S. R. 24s East West

County: Graham

Date Well Completed: 5/70

Plugging Commenced: 4/17/06

Plugging Completed: 4/17/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	Surface	187	8 5/8	187	0
	Production	Surface	4074	4 1/2	4074	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Swift Services. Tied onto tubing. Pumped 135 sx SMD & 450# hulls. Pulled tbg to 1074'. Pumped 40 sx & 75 # hulls to circ cement to surface. TOH w/tbg. Tied onto 4 1/2" csg. Pumped 20 sx 75# hulls, max press 400#, ISIP 375#. Tied onto 8 5/8". Pumped 20 sx 100# max press, 100# ISIP. Plugged @ 11:30 am. Witnessed by Darrel Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606

Address: 250 N. Water, Suite 300 ; Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc.


State of Kansas County, Sedgwick, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 250 N. Water, Suite 300; Wichita, KS 67202



Susan Brady My Commission Expires: 11-4-07

Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT