

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: AMERICAN WARRIOR, INC.
Address: P.O. Box 399 Garden City, KS 67846
Phone: 620 1275-9231 Operator License #: 4058
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 4/2/06 (Date)
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 065-23,161-00-00
Lease Name: TYNER-STEHRNO
Well Number: 1-32
Spot Location (QQQQ): _____ - SW - NW - SW
1820 Feet from North / South Section Line
100 Feet from East / West Section Line
Sec. 32 Twp. 7 S. R. 21W East West
County: Graham
Date Well Completed: 4/2/06
Plugging Commenced: 1:30PM 4/2/06
Plugging Completed: 3:15PM 4/2/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	222	8 5/8	221.67	None


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 1775'W/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes W/54Vis Mud
2nd Plug @ 875'W/100sks 15sks In Rat Hole Plugs displaced with mud
3rd Plug @ 275'W/40sks Total 200sks 60/40Poz 6%Gel W/1/4CF/sk By Allied Cementing
4th Plug @ 40'W/10sks Completed @ 3:15PM 4/2/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
Address: P.O. Box 763 Hays, KS 67601

Name of Party Responsible for Plugging Fees: AMERICAN WARRIOR, INC.

State of Kansas County, Ford, ss.
Nancy E Davis, Compliance Coordinator (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 ERICA KUHLMEIER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

(Signature) [Signature]
(Address) 1/4 American Warrior, Inc, P.O. Box 399, Garden City, KS 67846

SUBSCRIBED and SWORN TO before me this 19th day of May, 2006.
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 22 2006
KCC WICHITA
ACT