

#4

API NUMBER _____

LEASE NAME Stamper

WELL NUMBER 1

SPOT LOCATION SW SW NE

SEC. 10 TWP. 8 RGE. 17 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 12-5-89

Plugging Completed 12-5-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

Okmar Oil Company

LEASE OPERATOR _____

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas 67601

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
 DEPARTMENT OF REVENUE
 DEC 11 1989
 CONSERVATION DIVISION
 Wichita, Kansas

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled |
|-----------|---------|------|------|-------|--------|--------|
| | Surface | 0 | 148 | 8 5/8 | | |
| | Casing | 0 | 3397 | 5 1/2 | | None |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Tubing at 2500', BJ pump 150 sks. 65/35 pos, 8% gel, 1/4# floweal with 100# hulls. Pull tubing to 1250'. Pump 225 sks. 65/35 pos, 8% gel, 1/4# floweal with 700# hulls. Pull tubing. Hook to annulus pump 30 sks. 65/35 pos, 8% gel, 1/4# floweal with 100# hulls. Fill casing with 20 sks. 65/35 pos, 8% gel, 1/4# floweal. Annulus 500#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address Box 723 Hays, Kansas 67601

BJ Titan cementer

STATE OF Kansas COUNTY OF ELLIS, ss.

Mr. Ted Crawford

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Mo. 67601

SUBSCRIBED AND SWORN TO before me this 8 day of December, 1989

Boenay Smith
 Notary Public

My Commission expires: 5/1/1991