

STATE CORPORATION COMMISSION  
20 Colorado Dorby Building  
Topeka, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A  
LEASE NAME Krug  
WELL NUMBER 8

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

990 Ft. from S Section Line  
330 Ft. from X<sup>W</sup> Section Line

LEASE OPERATOR T. O. Rush  
ADDRESS Box 327 Haysville, Ks. 67060

SEC. 19 TWP. 8S RGE. 17W(E) or (W)  
COUNTY Rooks

PHONE # ( ) 773-1247 OPERATORS LICENSE NO. 3846

Date Well Completed \_\_\_\_\_

Character of Well oil

Plugging Commenced 12-8-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-9-88

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Hays, Ks. Dennis Hammel

ACC-1 filed? unknown If not, is well log attached? N/A

Producing Formation Kc. Depth to Top 3129 Bottom 3326 T.D. 3409

Give depth and thickness of all water, oil and gas formations.

WATER, GAS OR WATER RECORDS

CASING RECORD

Formation	Conten.	From	To	Size	Put In	Pulled out
		0	3409	5 1/2	3409	None
		0	1319	8 5/8	1319	None

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 14 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Run tubing to 3100' pumped 50 sacks Common W/2% KCL, Run tubing to 2700' pumped 40 sacks cement with 6 sacks hulls, Run to 1350' pumped 50 sacks ATL and 1 hull, Run to 700' pumped 125 sacks cement and 2 hulls, Pumped top of 5 1/2 with 25 sack cement and 1 hull at 100lbs (held)  
Pumped 75 sacks cement and 2 hulls down 8 5/8 and 5 1/2 at 100 lbs. (held)  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Corp. License No. 5822

Address Box 327 Haysville, Ks. 67060

STATE OF Kansas COUNTY OF Sedgwick, ss.

T. O. Rush (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) T. O. Rush

(Address) Box 327 Haysville, Ks. 67060

SUBSCRIBED AND SWORN TO before me this 12 day of December, 19 88

Gary D. Stearns  
Notary Public

My Commission Expires: 2-19-92

